

Name of work : Capital dredging for the manoeuvring basin of Indian Navy  
North Jetty basin at Naval Base, Kochi

Item No	Description of item	Unit	Rate
1	Dredging by deploying Grab Hopper Dredger and or Trailing Hopper Suction Dredger or any other suitable dredgers at the location of proposed manoeuvring basin of North Jetty under construction for Indian Navy at Cochin Port in the Ernakulam channel to a depth of (-)10.0m CD and disposing/dumping the dredged material evenly in the locations specified in the attached Drawing (Annexure III), including cost of conducting all surveys, mobilisation of the equipments cost/hire charges of survey launch, all plants, labour, material, etc complete as per directions of the Engineer in charge.		
	(i) Sea side of Jetty [depth (-) 10.m CD]	One Cubic meters	
	(ii) Lee side and under side of jetty with double handling [depth varying from (-)2.0m CD to (-)6.0m CD]	One Cubic meters	
2.	<p><b>Note:</b></p> <p>(i) GST shall be shown separately.</p> <p>(ii) No mobilization and demobilisation charges for dredger(s) will be paid extra and the rate shall cover both mobilization and demobilisation charges of dredger(s).</p> <p>Quantity shall be assessed based on the pre and post dredge surveys</p>		